



## PALOMINO DRIVE - PINE TOWNSHIP, PA

### PROJECT DESCRIPTION

This resurfacing project in Pine Township, PA was done on a **residential cul-de-sac that had suffered years of reflective and alligator cracking**. The objective was to compare the performance of a FORTA-FI<sup>®</sup> reinforced mix with a traditional mix, without fiber. The road was milled 1-1/2" and a 1-1/2" wearing course was placed, one side reinforced with a FORTA-FI<sup>®</sup> mix and one side with traditional asphalt, without fiber.

### UPDATE

The project was surveyed in 2017 and updated pictures were taken. **The side of the road reinforced with FORTA-FI<sup>®</sup> performed significantly better than the side of the road with traditional asphalt.**

### KEY POINTS

- Extended Pavement Life
- Reduced Rutting & Raveling
- Reduced Cracking

### DETAILS

**Date:** August 2012

**Location:** Pine Township - Wexford, PA

**Tonnage:** 700

**Fiber:** FORTA-FI<sup>®</sup>

Contact us for more details